Chanakya National Law University

Nyaya Nagar, Mithapur, Patna-800001

Date: - 26.10.2026

CORRIGENDUM RELATED TO NIT-44/2026-27 Dated 09.10.2026

PRE-BID QUERY & CLARIFICATION
PRE-BID DATE AND TIME: 24.10.2026 AT 03:00 PM

Name of Work: Refurbishment and Modernization of the existing library to integrate additional programmatic components, including breakout spaces, exhibition area, faculty room etc. in CNLU, Patna.

Query No.	Page No.	Particulars as uploaded in the tender document	May be Read as
1	01	Time of Completion (Point No. 06 at Pg No. 01	No Change
	102	Time allowed for execution of work – 10 Months Clause 05 mentioned at Pg. No. 102	May be read only 06 Months as mentioned at Point No. 06 of Pg. No. 01
2.	BOQ ITEM No. 10 AT PAGE NO. 125	Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealent over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes, wire mesh and silicon sealent shall be paid separately) Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. 4.) Three track three panels sliding window with fly proof S.S wire mesh (Two nos. glazed & one no. wire mesh panels) made of (big series) frame 116 x 45 mm & sash 46 x 62 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension. (Area of window above 1.75 sqm).	Rate is including wire mesh, silicon sealant and 5.5 mm clear glass.

26/10/26

3.		The contractor or his identified Sub-contractor should possess required valid license for executing the water supply / sanitary engineering works and should have executed similar water supply / sanitary engineering works for a minimum amount as indicated in Appendix in any one year.	No Change
4.		10% Lower Bidding Limit (RCD Notification): The Road Construction Department (RCD), Govt. of Bihar recently issued a Notification (Memo No. 7461 (S) dated 13.10.2026 - Copy attached) reinstating the lower bidding limit.	As per the notification issued by RCD memo no. प्र०–06 / द०वि० नियम 03–08 / 06 (अंश) 7461 (S) / पटना दिनांक 13.10. 2026 RCD, the applicable condition regarding the permissible minimum limit of quoted rates shall be followed. The quoted rate shall not be more below than 10%, BOQ Amount cost. Any bid quoting rate beyond the permissible limit shall not be considered valid.

Note: The other terms and conditions will remain same.

REGISTRAR

26/10/26

बिहार सरकार
पथ निर्माण विभाग
अधिसूचना

ज्ञापांक–प्र०–6 / द0वि0 नियम–03–08 / 06(अंश) 2461(S) / पटना, दिनांक– 13/10/2026

पथ निर्माण विभाग के अधिसूचना संख्या–447(S) सहपठित ज्ञापांक–448(S) दिनांक–16.01.2020 द्वारा प्रतिशत दर निविदा (percentage rate tender) पद्धति में सभी प्रकार की निविदाओं में निविदित दर की न्यूनतम अधिसीमा को समाप्त करने के संदर्भ में आदेश निर्गत है।

उक्त अधिसूचना को निरसित करते हुए पथ निर्माण विभाग के पत्रांक–2046(S) दिनांक–06.03.2014 द्वारा निरूपित प्रतिशत दर निविदा में न्यूनतम दर सीमा 10% (दस प्रतिशत) को पुनः बहाल किया जाता है। परिमाण विपत्र से 10% (दस प्रतिशत) से ज्यादा कम दर उद्धृत रहने वाली निविदायें अमान्य मानी जायेगी।

परिमाण विपत्र के दर से नीचे निविदित दर दिये जाने की स्थिति में अतिरिक्त कार्य प्रतिभू (Additional Performance Guarantee) लेने का निम्नांकित प्रावधान किया जाता है :–

1. परिमाण विपत्र की दर से 0 से 5 प्रतिशत कम उद्धृत दर वाले निविदा के लिए 0.25% अतिरिक्त कार्य प्रतिभू (Additional Performance Guarantee) प्रति एक प्रतिशत उद्धृत दर के लिए ली जाय।

2. परिमाण विपत्र की दर से 5 से 10 प्रतिशत कम उद्धृत दर वाले निविदा के लिए 0.5% अतिरिक्त कार्य प्रतिभू (Additional Performance Guarantee) प्रति एक प्रतिशत उद्धृत दर के लिए ली जाय।

यह आदेश तत्काल प्रभाव से प्रभावी रहेगा।

बिहार राज्यपाल के आदेश से

ह0 / –
(पंकज कुमार पाल)
सचिव
पथ निर्माण विभाग, बिहार, पटना।

(19)

प्रेस नोट

पथ निर्माण विभाग द्वारा प्रतिशत निविदा पद्धति में निविदित दर की न्यूनतम सीमा को निम्नरूपेण निर्धारित किया गया है:–

(i) पथ निर्माण विभाग के पत्रांक–2046 (S) दिनांक–06.03.2014 के द्वारा निरूपित Percentage दर निविदा में न्यूनतम दर सीमा 10% (दस प्रतिशत) को पुनः बहाल करते हुए प्रतिशत दर (In Percentage rate tender) पद्धति में प्राप्त की जाने वाली सभी प्रकार की निविदाओं में निविदित दर की न्यूनतम अधिसीमा परिमाण विपत्र की दर (राशि) से 10 प्रतिशत कम तक निर्धारित किया जाता है। 10 प्रतिशत से ज्यादा कम दर उद्धृत रहने वाले निविदाएं अमान्य मानी जायेगी।

(ii) परिमाण विपत्र के दर से नीचे निविदित दर दिये जाने की स्थिति में अतिरिक्त कार्य प्रतिभू (Additional Performance Guarantee) लेने का निम्नांकित प्रावधान लागू रहेगा :–

(a) परिमाण विपत्र की दर से 0 से 5 प्रतिशत कम उद्धृत दर वाले निविदा के लिए 0.25% अतिरिक्त कार्य प्रतिभू (Additional Performance Guarantee) प्रति एक प्रतिशत उद्धृत दर के लिए ली जाय।

(b) परिमाण विपत्र की दर से 5 से 10 प्रतिशत कम उद्धृत दर वाले निविदा के लिए 0.5% अतिरिक्त कार्य प्रतिभू (Additional Performance Guarantee) प्रति एक प्रतिशत उद्धृत दर के लिए ली जाय।

(पंकज कुमार पाल)
सचिव
पथ निर्माण विभाग, बिहार, पटना।